



Project: Wildcat Road Bridge

Project Completed: 2013

Overview: Full in-kind repair and restoration of this historic metal truss bridge for continued vehicular use. Steel work: Bach Steel was responsible for repair of existing steel, including heat straightening of truss members and bracing as needed, riveting of replacement/replicated sections including base of end posts.



Truss before restoration, after deck removal.



Restored truss with new deck installed.



Truss before restoration, after deck removal.



Replicated bridge shoe and endpost base.



Replica attachments for the overhead lateral bracing had to be made. Original attachment in lower portion of photo, replica is above.



Repainting the bridge.



Repainting the bridge.



Restored and repainted truss awaiting deck stringers and a new deck.



Installing the new deck.



Bridge with new deck in place.



Bridge with new deck in place.



View of the bridge a couple years after it had been completed.



Phone:

[517-581-6243](tel:517-581-6243)

Email:

nels@bachsteel.com

Mailing Address:

Bach Ornamental and Structural Steel, Inc.
4140 Keller Road
Holt, MI 48842-1254

Website:

bachsteel.com

Facebook:

facebook.com/bachsteel